

MAY 4 1987 15.159.00433.0000

5 020342

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 12-28-61  
C SE NE, SEC. 21, T 20 S, R 6 W/EX  
3300 feet from S section line  
660 feet from E section line  
Lease Name FRY "C" Well # 1  
County Rice 110.11  
Well Total Depth 3388 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 164-140 sks

TECHNICIAN'S PLUGGING REPORT

Operator License # 9339

Operator: K & K Oil Company  
Name & Address Box 176  
Chase, Kansas 67524

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347 Chase, Kansas 67524

Company to plug at: Hour: 10:00 a.m. Day: 4 Month: May Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316 938-2457

were: Fill hole with sand to 3300' and cement with 5 sacks cement. Set rock bridge from 350' to 325' and cement with 5 1/2 yards ready-mix to base of cellar.

Plugging Proposal Received by Phil Worley  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:45 p.m. Day: 4 Month: May Year: 19 87

ACTUAL PLUGGING REPORT Filled hole with sand to 3300' and cemented with 5 sacks. Bailed hole from 70' to 370'. Set Rock Bridge from 370' to 345' and cemented hole to base of cellar with 6 yards ready-mix.

5 1/2-3387-50 sacks PBTD-3379' Perfs 3367'-3375'

Remarks: 2900' of 5 1/2" casing recovered Mid America Redi-Mix, Inc. cons. 10000 COMMISSION  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-15-87

INV. NO. 16907

Signed [Signature] RECEIVED  
MAY 12 1987  
CONSERVATION DIVISION  
Wichita, Kansas



*"Transit-Mixed Concrete"*  
**MID-AMERICA REDI-MIX, INC.**

2510 W. Blanchard  
 So. Hutchinson, KS 67505  
 (316) 663-1559  
 (Main Plant)

Box 470, Lyons, KS 67554  
 (316) 257-5602  
 or  
 (316) 257-2161

ORDER NO. 001131 5/4 1987

DELIVER TO Kelso Army Bldg JOB NO. \_\_\_\_\_

ADDRESS Spina Rd to 3rd St, Hutchinson

CHARGE TO 1/2 No Backin W. side CAUTION: \_\_\_\_\_

ADDRESS Spina "Q" #1

QUANTITY	ITEM	PRICE	AMOUNT
6	MIX 11 TRANSIT-MIX CONCRETE		
	CEMENT		
	ROCK		
	SAND		
	CONCRETE ACCELERATOR		
	HOT WATER		
	ROAD SAND	GROSS	
	CONCRETE SAND	TARE	
	FILL SAND	NET	
	OTHER		
	TIME	OUT	JOB
			RETURN

DRIVER: Note here if water has been added and how much.	IMPORTANT: We cannot be held responsible for damage caused by our trucks when delivering material beyond the curb line. Not responsible for quality of concrete if water is added by purchaser.	MDSE. TOTAL
		SALES TAX
DRIVER <u>Wayne</u>	TRUCK NO. <u>19</u>	TOTAL AMT. DUE

All Claims and Returned Goods must be accompanied by this bill - All accounts DUE and PAYABLE 10th. of following month. All accounts not paid in 30 days interest charged at 1 1/2 percent per month (ANNUAL PERCENTAGE RATE 18%).

EXTRA CHARGE MADE FOR EXCESS UNLOADING TIME

Rec'd By \_\_\_\_\_

1009

CAUTION: Freshly mixed cement, mortar, grout or concrete may cause skin irritation. Avoid direct contact where possible and wash exposed skin areas promptly with water. If any cementitious material gets into the eye, rinse immediately and repeatedly with water and get prompt medical attention. KEEP OUT OF REACH OF CHILDREN

PLANT

*[Faint handwritten notes and stamps at the bottom right of the page]*