

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00997-00-00
Spot: CNENWSW Sec/Twnshp/Rge: 11-17S-10W
2310 feet from S Section Line, 990 feet from W Section Line
Lease/Unit Name: FREVERT Well Number: 2
County: ELLSWORTH Total Vertical Depth: 3294 feet

Operator License No.: 5427
Op Name: LAUCK, D.R. OIL CO., INC.
Address: 221 S. BROADWAY, STE 400
WICHITA, KS 67202

Conductor Pipe: Size feet: 8107.06
Surface Casing: Size 10 feet: 189 185 SX CMT
Production: Size 5.5 feet: 3243 50 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/04/2002 1:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JOE STRUBE Company: D.S&W WELL SERVICE INC Phone: (620) 587-3361

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/04/2002 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sand open hole with 5sxs cement on top, perf. @ 1190' and pump 35sxs w/100lbs cotton hulls, perf @ 938' and pump 35sxs w/100lbs cotton hulls, perf @ 240' and circulate cement w/300lbs hulls to surface. Pumped approx 30sxs down surface casing and held 140-150lbs pressure.

RECEIVED
KCC DISTRICT #2

APR 11 2002

WICHITA, KS

Remarks: 60-40 POZ-MIX, 4% GEL, ALLIED CEMENT TICKET # 8095

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE

4-16-02

NV. NO.

2002061665