

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-01008-00-01
Spot: CSENE SW Sec/Twnshp/Rge: 11-17S-10W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: FREVERT Well Number: 7 /
County: ELLSWORTH Total Vertical Depth: 3344 feet

Operator License No.: 5427
Op Name: LAUCK, D.R. OIL CO., INC.
Address: 221 S. BROADWAY, STE 400
WICHITA, KS 67202

Conductor Pipe: Size feet: 8108.68
Surface Casing: Size 10.75 feet: 206 108 SX CMT
Production: Size 5.5 feet: 3233 50 SX CMT
Liner: Size feet:

Well Type: SWD UIC Docket No: D23945.0 Date/Time to Plug: 01/16/2002 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: MELVIN G. URBAN Company: D.R. LAUCK OIL CO., INC. Phone: (620) 564-2013

Proposed Plugging Method:

See actual report.

Plugging Proposal Received By: DAVE WERTZ Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/16/2002 3:20 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sand open hole w/22sxs sand and put 15sxs cement on top, perforate @ 1190' and pump 35sxs, perforate @ 938' and pump 35sxs, perforate @ 260' and circulate cement to surface w/ 200lbs hulls.

RECEIVED
KCC DISTRICT #2

JAN 18 2002

WICHITA, KS

Remarks: ALLIED CEMENT # 10431. 60/40 POZ-MIX, 4% GEL. 300LBS COTTON HULLS ADDED AT 1190' PLUG AND 93

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED

DATE Jan 23, 02

WV. NO. 2002061296