

10-6

RECEIVED
KANSAS CORPORATION COMMISSION

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

OCT 14 1993

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15.053.00996.0000

 CNL NE SW , SECTION 11 TOWNSHIP 17 RANGE 10W

OPERATOR LICENSE # 5427

 FEET FROM S SECTION LINE
 FEET FROM E SECTION LINE

OPERATOR D R LAUCK OIL CO INC
NAME & 221 S BROADWAY, #400
ADDRESS WICHITA KS 67202

LEASE NAME: FREVERT #1
COUNTY: ELLSWORTH
WELL TOTAL DEPTH: 3269'

106,24

PIPE:
SURFACE CASING: 10" @ 160'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: KELSO CASING PULLING
ADDRESS: CHASE KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 6 MONTH: 10 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: MELVIN URBAN
COMPANY NAME: PHONE:

WERE: SAND TO 3150' & 10 SX - 70 SX @ 830 - 350' TO SURF

PLUGGING PROPOSAL RECEIVED BY: M. L. KORPHAGE

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 3:30 DAY: 6 MONTH: 10 YEAR: 1993

ACTUAL PLUGGING REPORT:

SANDED BOTTOM TO 3150' & 10 SX OF COMMON - PERF 5-
1/2" CSG @ 830' AND AT 350' - RAN TUB & PKR TO 805' -
PUMPED 70 SX - PULLED TO 350' - GOT CIRC BUT COULD NOT
GET CMT TO COME AROUND - RAN TUB TO 660' & PUMPED 35 SX
- SHUT DOWN FOR 24 HOURS - PULLED ALL TUBING TIED TO
THE 5-1/2" - GOT GOOD CIRC - PUMPED 124 SX - GOT GOOD
CMT ON BACKSIDE AND INSIDE 5-1/2" CSG.

REMARKS: ALLIED #5450 60/40 4%

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 10-21-93

INV. NO. 38993

[Signature]

JACK LUTHI

(AGENT)