

11-30

RECEIVED
KANSAS CORPORATION COMMISSION

15.053.01010.0000

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

DEC 10 1993

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 1930 OIL WELL

NE SE SW, SECTION 11 TOWNSHIP 17 RANGE 10W

OPERATOR LICENSE # 5427

990 FEET FROM S SECTION LINE
2970 FEET FROM E SECTION LINE

OPERATOR D. R. LAUCK OIL COMPANY

NAME & 221 S BROADWAY, #400

ADDRESS WICHITA KS 67202

LEASE NAME: FREVERT #9

COUNTY: ELLSWORTH 106.05

WELL TOTAL DEPTH: 3263' PBDT 3263'

PIPE: 5-1/2" @ 3234' / 50 SX

SURFACE CASING: 10" @ 202'

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SMD ☐ D&A ☐

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: KELSO CASING PULLING

ADDRESS: P O BOX 347, CHASE, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: AM DAY: 30 MONTH: 11 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: KELSO CASING PULLING PHONE: 316-938-2943

WERE: CSG PARTED @ 1160' - TUB & ANCHOR CATCHER ARE BELOW
1160' - SHOOT @ 3010' - RUN TUB TO 3010' & PUMP 35 SX
CMT - PUMP 35 SX THRU CSG @ 1200' - PULL CSG TO 900' -
35 SX CMT - PULL CSG TO 250' - CIRC CMT TO SURF

PLUGGING PROPOSAL RECEIVED BY: DISTRICT 2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (☒) PART (☐) NONE (☐)

COMPLETED: HOUR: 4:00P DAY: 30 MONTH: 11 YEAR: 1993

ACTUAL PLUGGING REPORT:

CSG PARTED @ 1160' - TUB & ANCHOR CATCHER ARE BELOW
1160' - SHOT @ 3043' & 35 SX CMT THRU TUB - PULLED CSG
TO 1151' & 35 SX - PULLED CSG TO 928' & 35 SX - PULLED
CSG TO 288' & 150 SX CMT CIRC TO SURF - RECOVERED 1160'
OF 5-1/2"

REMARKS: OH 3234-63' - ALLIED #1643 60/40 POZ 4% GEL

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE DEC 13 1993

INV. NO. 39491

R PHIL WORLEY

(AGENT)

FORM CP-2/3
REV. 3/90