

5 030295

8-6-87

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 113-20,975.0000

SW , SEC. 2 , T. 20 S, R. 4 WXXX  
330 feet from S section line

3880 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8653

Lease Name Southwestern College Well # 1-A

Operator: Petroleum Technologies, Inc.

County McPherson 126.26

Name & Address 3535 Broadway, Suite C

Well Total Depth 3885 feet

Kansas City, MO 64111

Conductor Pipe: Size 13 3/8 feet 225

Surface Casing: Size 8 5/8 feet 705

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: \_\_\_\_\_ Day: 28 Month: 7 Year: 19 87

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) \_\_\_\_\_

were: 5 1/2" @3885' w/200 sxs. Perfs 3710-32. Sand to 3600, cap w/6 sxs cement by bailer. Recovered 2500' of 5 1/2" casing. Pump 75 sxs cement, 12 gel, 15 sxs cement down 8 5/8" casing. Run 1" down 13 3/8" as far as possible. Cement to surface with approximately 15 to 20 sxs cement.

Plugging Proposal Received by Warren Kirkpatrick  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ Top \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:00pm Day: 6 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT Sand to 3600', capped w/6 sxs cement. Recovered 2500' of 5 1/2" casing. Ran 1" tubing down 13 3/8" to approximately 40'. Circulate cement to surface (5 bbl slurry). Pumped 4 sxs gel (8 bbls slurry) followed w/21 bbls cement slurry, followed with 25 bbls of gel slurry, followed w/3 1/2 bbls cement slurry. Mas PSI-- 700#. Shut in with 250 # PSI. Used 110 sxs 60/40 6% gel, 15 sxs gel.

AUG 12 1987

Remarks: Howco #583227-7 B-74511

(If additional description is necessary, use BACK of this form.)

**INVOICED**

(If possible) observe this plugging.

DATE 8-14-87

Signed Merlan Lunsell  
(TECHNICIAN)

INV. NO. 17822 SEP 17 1987

8-6