

1030176

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,116.0000

SW NE NE , SEC. 3 , T 20 S, R 16 W/E

990 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6343

Lease Name Fleske Well # 1

Operator: Yost Oil Operations, Inc.

County Pawnee

Name & Address Box 811

Well Total Depth 3739 121.52 feet

Russell, KS 67665

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 318

RECEIVED

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ STATE CORPORATION COMMISSION S/W Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_ MAY 18 1984

Plugging Contractor Emphasis Oil Operations License Number 8241

CONSERVATION DIVISION  
Wichita, Kansas

Address Box 506, Russell, KS 67665

Company to plug at: Hour: 4:00 am Day: 13 Month: May Year: 19 84

Plugging proposal received from Greg Flax

(company name) Emphasis (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3630' with 50 sx cement 2nd plug at 1030' with 50 sx cement

3rd plug at 400' with 50 sx cement and 3 sx flowseal  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Shumant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 1:00 pm Day: 13 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 3630' with 50 sx cement, 2nd plug at 1030' with

50 sx cement, 3rd plug at 400' with 50 sx cement and 3 sx flowseal, 4th & 5th plugs -

solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug

to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Water flowed through cement after pumping cement. Squeezed through surface pipe with 250

sx of Allied Special Cement. Shut in well with 100# pressure

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. Also used Allied Special Cement.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 5-21-84

Signed Steve Shumant  
(TECHNICIAN)

INV. NO. 1584

5-13