

6-050095

12-1

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-24,157.0000

NW NW NE /4 SEC. 15, 20 S, 14 W
4950 feet from S section line
2310 feet from E section line

Operator license# 30606 Lease Unruh well # 1-15
Operator: Murfin Drilling Co. County Barton
Address: 250 N. Water Well total depth 3700 feet
Suite 300 Conductor Pipe: inch @ feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 815 feet

120.25

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: P. O. Box 347, Chase, Kansas 67524

Company to plug at: Hour: PM Day: 1 Month: December Year: 1992

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pulling phone:

Were: PBTD 3650'. Perfs at 3507' to 3557'. 8 5/8" set at 815 w 400 sx.
4 1/2" set at 3694' w 115 sx. Bottom sanded to 3450', bailed down 4 sx
cement. Shot pipe at 2747'. Pulled to 1600', ran 20 sx 60/40 poz mix,
8% gel. Pulled pipe to 800', pumped 70 sx 60/40 poz mix, 8% gel. Pulled
pipe to 400', pumped 100 sx 60/40 poz mix, 8% gel, circulated cement.
Pulled 400' of pipe, topped off hole with 20 sx 60/40 poz mix, 8% gel.

Plugging Proposal Received by: Bruce Basye
Plugging operations attended by agent? All[XXX], Part[], None[]

Completed: Hour: 2:30 PM, Day: 1, Month: December, Year: 1992

Actual plugging report: Plugged as described above.

Remarks: Allied cementing

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1992

I did[XX] / did not[] observe the plugging.

Bruce Basye
CONSERVATION DIVISION
WICHITA, KANSAS

Bruce D. Basye
(agent)
Form CP-2/3

INVOICED

DATE 1-8-93
INV. NO. 37152

TD