

To: 6 061442  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 009-24,123.0000

SE, SEC. 29, T 20 S, R 15 W/E  
660 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5591

Lease Name Maneth Well # 1

Operator: Westech Energy Co Inc.  
Name &  
Address Box 949  
Great Bend, Ks. 67530

County Barton 126.75  
Well Total Depth 3900 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 990

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhole Engineering, Inc. License Number 5111

Address Box 698, Great Bend, Ks. 67530

Company to plug at: Hour: 9:00 AM Day: 1 Month: March Year: 19 88

Plugging proposal received from D. B. Pullie

(company name) Rockhole Engineering Inc. (phone) 316-792-2506

were: Order 125 sks 65/35 Poz 10% Ge1 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:00 AM Day: 1 Month: March Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 990' w/200 sks. 5 1/2" set at 3871' w/150 sks.

Top perf at 3751'. Plugged bottom w/sand and 5 sks cement to 3700'. Shot pipe one  
time and recovered 2800'. Pumped in 8 5/8" 25 sks cement w/5 sks Hulls in 100 sks  
cement w/900 Psi.

RECEIVED  
STATE CORPORATION COMMISSION

MAR - 9 1988

Remarks: By Allied.  
(If additional description is necessary, use BACK of this card)

CONSERVATION DIVISION  
WICHITA, KANSAS

INVOICED  
(If desired, please observe this plugging.)

Signed Gilbert G. Scheck  
(TECHNICIAN)

Gilbert G. Scheck

DATE 3-10-88

NV. NO. 20078

3-1