

1 060693

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,224 . 0000

C E/2 E/2 NESEC. 7 , T 20 S, R 16 (W/E)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418

Operator: Allen Drilling Company
Name & Address: P. O. Box 1389
Great Bend, KS 67530

3960 feet from S section line

330 feet from E section line

Lease Name Russell Well # 1-7

County Pawnee 125.61

Well Total Depth 3865 Arbuckle feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1135

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address P. O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 4:00 pm Day: 22 Month: October Year: 19 85

Plugging proposal received from Steve Dunham

(company name) Allen Drilling (phone) 316-793-5877

were: to fill hole with heavy mud and spot cement through drill pipe Elevation N/A
Anhydrite 1125-55'

1st plug in the Arbuckle with 50 sx cement if in 50' or more

2nd plug 30' below the base of the surface pipe with 50 sx cement

3rd plug at 400' with 30 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement
Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:45 pm Day: 22 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3820' with 50 sx cement, 2nd plug at 1170' with 50
sx cement, 3rd plug at 400' with 30 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1985

Remarks: Used 60/40 Pozmix 6% gel by Halliburton
(If additional description is necessary, use BACK of this form.) CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE OCT 29 1985

INV. NO. 10763

Signed Paul A. Luthi
(TECHNICIAN)