

1 051066

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-5-88
API NUMBER 15- 145-21,284 .0000

NE SW NE, SEC. 7, T 20 S, R 16 W EX

3630 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408

Lease Name Russell Well # 1

Operator: Trans Pacific Oil Corporation

County Pawnee 126.10

Name & Address 410 One Main Place

Well Total Depth 3880 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 431

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Trans Pac Drilling, Inc. License Number 5841

Address 410 One Main Place, Wichita, KS 67202

Company to plug at: Hour: 12 p.m. Day: 5 Month: 7 Year: 19 88

Plugging proposal received from Gary Pugh

(company name) Trans Pac Drilling, Inc. (phone) 316-262-3596

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1153-1180' Elevation 2100'

1st plug at 1180' with 50 sx cement, 2nd plug at 450' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 5 Month: 7 Year: 1988

ACTUAL PLUGGING REPORT 1st plug at 1180' with 50 sx cement,

2nd plug at 450' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-21-88

INV. NO. 21549

Signed Richard W. Lacey (TECHNICIAN)

15.145.21284.0000

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL 145-21, 284

CORRECTED API #

(see rules on reverse side)

Expected Spud Date: 6 month 30 day 88 year

* API Number 15-145-21,284

OPERATOR: License # 09408
Name Trans Pacific Oil Corporation
Address 410 One Main Place
City/State/Zip Wichita, Ks. 67202
Contact Person Alan D. Banta
Phone 316-262-3596

NE SW NE Sec. 7 Twp. 20 S, Rg. 16
3630 Ft. from South Line of Section
1650 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County Pawnee

CONTRACTOR: License # 05841
Name Trans Pac Drilling, Inc.
City/State Wichita, Ks. 67202

Lease Name Russell Well # 1

Well Drilled For: Well Class: Type Equipment:
Oil Storage Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Ground surface elevation feet MSL

Domestic well within 330 feet: yes x no

Municipal well within one mile: yes x no

Depth to bottom of fresh water 100

Depth to bottom of usable water 380

Surface pipe by Alternate: 1 x 2

Surface pipe planned to be set 400

Conductor pipe required 3850

Projected Total Depth feet

Formation Arbuckle

If OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 6/27/88 Signature of Operator or Agent Title Office Manager

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 400 feet per Alt. 1 X

This Authorization Expires 12-27-88 Approved By 6-27-88

EFFECTIVE DATE: 7-2-88

* WAS: 151-21,891

6-29-88

400+ - 8 7/8 Dick Rapco

9N 1-W
1-N

PUSHER Gary Pugh
TD 3880' FORMATION Arb. 23' into
SURFACE PIPE 8 5/8" @ 431'
ANHYDRITE 1153-1180' ELEVATION 2100'
STARTING TIME & DATE 12:00p 7-5-88
COMPLETION TIME & DATE 2:30p 7-5-88
1st PLUG @ 1180 FT. W/ 50 SX
2nd PLUG @ 450 FT. W/ 40 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied
TECHNICIAN D.G. Lacey sawall 6/40 6/7

RECEIVED
STATE CORPORATION COMMISSION
7 1988
CONSERVATION DIVISION
Wichita, Kansas