

1050482

API NUMBER 15- 135-22,791 . 00.00 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE SW, SEC. 12, T 19 S, R 25 W/EX

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Clark Well # B1

Operator: VAC Petroleum Co.

County Ness 144.63

Name & Address 333 N. Rock Road, Suite 105

Well Total Depth 4450 feet

Wichita, KS 67206

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 1:00 pm Day: 21 Month: March Year: 19 85

Plugging proposal received from Mark Guinn

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2030' with 50 sx cement

2nd plug at 1000' with 50 sx cement

3rd plug at 480' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 pm Day: 21 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2030' with 50 sx cement, 2nd plug at 1000' with

50 sx cement, 3rd plug at 480' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

APR 04 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 4-12-85

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 7693