

MAY 18 1987

To: 1 070340
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,107 · 00.00
C SE NW, SEC. 8, T 19 S, R 24 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Miner "A" Well # 3

Operator: Viking Resources
Name & Address: 120 South Market, Suite 518
Wichita, KS 67202

County Ness 142.87
Well Total Depth 4396 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A^X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling Inc. License Number 5420

Address 401 East Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 18 Month: 5 Year: 19 87

Plugging proposal received from Bob Kasper

(company name) White & Ellis Drilling Inc. (phone) 316-792-2424

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2343'
Anhydrite 1612-23'

- 1st plug at 1620' with 50 sx cement, 2nd plug at 990' with 80 sx cement,
- 3rd plug at 240' with 40 sx cement,
- 4th plug at 40' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part ^X None _____

Operations Completed: Hour: 10:20 a Day: 18 Month: 5 Year: 19 87

- ACTUAL PLUGGING REPORT
- 1st plug at 1620' with 50 sx cement,
 - 2nd plug at 990' with 80 sx cement,
 - 3rd plug at 240' with 40 sx cement,
 - 4th plug at 40' with 10 sx cement,
 - 5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel .3% cc by Allied.

(If additional description is necessary, use BACK of this form.)
I (old / ~~xxxxxx~~) observe this plugging.

DATE 5-19-87

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 16966

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 5 1 87 month day year

API Number 15- 135-23,107-00100

OPERATOR: License # 5011 Name Viking Resources Address 120 S. Market, Suite 518 City/State/Zip Wichita, Ks. 67202 Contact Person Jim Devlin Phone 262-2502

C SE NW Sec. 8 Twp. 19 S, Rg. 24 X West 3300 Ft. from South Line of Section 3300 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet County Ness

CONTRACTOR: License # 5420 Name White & Ellis Dkg. Fur. City/State Wichita, Kansas

Lease Name Miner "A" Well # 3 Ground surface elevation Unknown feet MSL

Well Drilled For: X Oil SWD X Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes Xno Municipal well within one mile: yes Xno

If OWWO: old well info as follows:

Depth to bottom of fresh water 80 Depth to bottom of usable water 775

Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate: 1 X Surface pipe planned to be set 200

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Conductor pipe required none Projected Total Depth 4400 feet Formation Miss

Date Signature of Operator or Agent James R. Devlin Title

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. 40 This Authorization Expires 10-2-87 Approved By 4-1-87

Spud 5-11 or 5-12-87 Set 200 +

C SE NW Sec. 8 Twp. 19 S, Rg. 24 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Base of Anhy. feet depth with 40 sxs of 60/40 Poz. 2nd plug @ 775 feet depth with 50 sxs of 60/40 Poz. 3rd plug @ 30' below base of surf. feet depth with 40 sxs of 60/40 Poz. 4th plug @ 0-40 feet depth with 10 sxs of 60/40 Poz. 5th plug @ feet depth with sxs of (2) Rathole with 15 sxs (b) Mousehole with 10 sxs

PUSHER Bob Casper TD 4396 FORMATION Miss SURFACE PIPE 8 3/8 @ 224 ANHYDRITE 1612-23 ELEVATION 2343 STARTING TIME & DATE 9:00am 5-18-87 COMPLETION TIME & DATE 10:20am 5-18-87 1st PLUG @ 1620 FT. W/ 50 SX 2nd PLUG @ 990 FT. W/ 80 SX 3rd PLUG @ 240 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Allied TECHNICIAN Dan saw part 60/40 60/40 3/6cc

RECEIVED STATE CORPORATION COMMISSION

CONSERVATION DIVISION Wichita, Kansas