

To: 071112 10-6
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,686.00.00870
NW SW SW, SEC. 23, T. 18 S, R. 26 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5184
Operator: Shields Oil Producers, Inc.
Name & Address: Shields Bldg.
Russell, KS 67665

1160 feet from S section line
4950 feet from E section line
Lease Name Floyd Well # 1
County Ness 147.55
Well Total Depth 4540 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 6 Month: 10 Year: 19 92

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4538' w/175 sx cement, PBTD 4509', Perfs at 4470-82'
1st plug sand back to 4400' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 50 sx cement at 1900' through casing,
3rd plug pump 80 sx cement at 1150', 4th plug pump 50 sx cement at 600',
5th plug pump 50 sx cement at 230', 6th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 6 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped through casing with 50 sx cement at 1900',
3rd plug at 1150' with 80 sx cement,
4th plug at 600' with 50 sx cement,
5th plug at 230' with 50 sx cement, 6th plug topped off with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1992

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied. Recovered 3132' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Dan Johnson
(TECHNICIAN)

INVOICED
DATE 10-29-92
INV. NO. 36645