

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-00999-00-00  
Spot: CSWNESW Sec/Twnshp/Rge: 11-17S-10W  
1650 feet from S Section Line, 1650 feet from W Section Line  
Lease/Unit Name: FREVERT Well Number: 4  
County: ELLSWORTH Total Vertical Depth: 3266 feet

Operator License No.: 5427  
Op Name: LAUCK, D.R. OIL CO., INC.  
Address: 221 S. BROADWAY, STE 400  
WICHITA, KS 67202

Conductor Pipe: Size feet: 4 1/2 106.15  
Surface Casing: Size 8.625 feet: 150 150 SX CMT  
Production: Size 5.5 feet: 3230 75 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/10/2002 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: MELVIN G. URBAN Company: DS&W WELL SERVICE Phone: (620) 564-2013

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/10/2002 10:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sand open hole and put 5sxs cement on top, perforate at 1190' and pump 35sxs perforate at 938' and pump 35sxs, perforate at 300' and circulate cement at surface w/150lbs cotton hulls. Pumped approx., 45sxs on backside of 5 1/2" in the 8 5/8" with 150lbs hulls-held 400lbs pressure.

RECEIVED  
KCC DISTRICT #2

APR 16 2002

WICHITA, KS

Remarks: ALLIED CEMENT TICKET #7596. 60/40 POZ, 4% GEL, 150SXS. 500LBS COTTON HULLS TOTAL. 200LBS USE

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-22-02

INV. NO. 2002061684