


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 29 Twp. 19 Rge. 21 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

C/SE/NE
Lease Owner The Maurice L. Brown Co.
Lease Name F. Rein Well No. 1
Office Address Suite 200 Sutton Place Bldg, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced December 14 19 77
Plugging completed December 20 19 77
Reason for abandonment of well or producing formation
depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4,520
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	554'	none
				5 1/2"	4510'	3,169'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped sand to 4400' and 5 sacks cement.
Shot pipe at 3600', 3520', 3300' and 3200'.
Pulled 77 joints 5 1/2" casing.
Squeezed well with 1 sack hulls, 15 sacks gel and 130 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 28 1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.
Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
Box 698, Great Bend, Kansas 67530
(Address)

Subscribed and Sworn to before me this 27 day of December 1977

My commission expires
ANITA L. BOGLE
Barton County, Kansas
My Appt. Exp. Nov. 21, 1981

Anita L. Bogle
Notary Public.

DRILLERS LOG

OPERATOR: Maurice L. Brown Company
200 Sutton Place Building
Wichita, Kansas 67202

Lease: F. Rein No. 1
C SE NE 29-19S-21W
Ness County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 9/9/77

COMPLETED: 9/20/77

RTD: 4520'

CASING: 8-5/8" set at 550' with 280 sacks cement

OIL STRING: 5-1/2" set at 4510' with 150 sacks cement

0' to 555' Shale (12½" Hole)
555' to 660' Shale
660' to 1509' Shale & Sand
1509' to 1539' Anhydrite
1539' to 2495' Shale & Shells
2495' to 4430' Lime & Shale
4430' to 4520' Lime
4520' RTD

STATE OF KANSAS

COUNTY OF SEDGWICK


I, James C. Rensberg of the Slawson Drilling Company, Inc.
hereby state that the above and foregoing is a true and accurate copy of
the log of the F. Rein No. 1 For Maurice L. Brown Company.

James C. Rensberg

Subscribed and sworn to me on this 29th day of September, 1977

Mary Lou Taylor
Mary Lou Taylor, Notary

My commission expires January 17, 1981



RECEIVED
STATE CORPORATION COMMISSION

DEC 01 1977

CONSERVATION DIVISION
Wichita, Kansas