

STATE OF KANSAS
STATE CORPORATION COMMISSION
290 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,248-00

LEASE NAME Watson

WELL NUMBER 1

330 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 23 TWP. 18 SRGE. 26 (R) or (W)

COUNTY Ness

Date Well Completed 6-2-88

Plugging Commenced 6-2-88

Plugging Completed 6-2-88

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Totten Resources, Inc.

ADDRESS 2506 Green Leaf Court, Wichita, KS 67226

PHONE# (316) 687-4959 OPERATORS LICENSE NO. 3567

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 1, 1988 (date)

by Steve Pfifer (KCC District Agent's Name).

Is ACO-1 filed? Will be by oper. If not, Is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4496'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

1st Plug set at 1863' w/50 sacks thru drill pipe

2nd plug set at 1032' w/80 sacks thru drill pipe

3rd plug set at 260' w/40 sacks thru drill pipe

4th plug set at 40' w/10 sacks thru drill pipe 15 sacks in the rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address 620 Hubbard, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) 620 Hubbard, Great Bend, KS

67530

SUBSCRIBED AND SWORN TO before me this 20 day of June, 1988

RECEIVED

STATE CORPORATION COMMISSION

Dorothy M. Hague
Notary Public

My Commission Expires 5-5-90

JUN 24 1988

Form CP-4
Revised 07-87

DRILLERS WELL LOG

DATE COMMENCED: 5-27-88

DATE COMPLETED: 6-2-88

Totten Resources, Inc.
WATSON #1
SW SE SE
Sec. 23-18S-26W
Ness County, KS

0	-	235'	Clay, Rock & Shale
235	-	1823'	Chale & Sand
1823	-	1863'	Anhydrite
1863	-	2028'	Shale & Lime
2028	-	3137'	Lime & Shale
3137	-	3278'	Shale & Lime
3278	-	3740'	Lime & Shale
3740	-	3950'	Shale & Lime
3950	-	4325'	Lime & Shale
4325	-	4496'	Lime
		4496'	RTD

Surface Pipe: Set new
8 5/8" at 233' with 140
sacks 60/40 Pozmix, 2%
Gel, 3% C.C.

A F F I D A V I T


STATE OF KANSAS
COUNTY OF BARTON) ss.

ERVIN NEIGHBORS of lawful age, does swear and state that
the facts and statements herein are true and correct to the best
of his knowledge.

Ervin Neighbors
Ervin Neighbors

SUBSCRIBED AND SWORN to before me this 3rd day of June, 1988.

DOROTHY M. HAGUE
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 5-5-90



Dorothy M Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUN 24 1988

CONSERVATION DIVISION
Wichita, Kansas