

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,686-00.00

LEASE NAME Floyd

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 23 TWP. 18S RGE. 26W (E) or (W)

COUNTY Ness

Date Well Completed

Plugging Commenced 9-29-92

Plugging Completed 10-6-92

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS 326 Main P.O. Box 709 Russell, Kansas 67665

PHONE#() OPERATORS LICENSE NO. 5184

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4540'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	208'	none
				5 1/2"	4538'	3181'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 4400', ran 5 sacks cement. Shot pipe @3527', 3318',
3181'. Pumped 50 sacks @1900', pulled to 1150' pumped 80 sacks, pulled
to 600' pumped 50 sacks, pulled to 230' pumped 50 sacks, pulled to 40'
pumped 10 sacks 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. RECEIVED

STATE CORPORATION COMMISSION

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc. **OCT 14 1992**

STATE OF Kansas COUNTY OF Rice, ss. **CONSERVATION DIVISION**
Wichita, Kansas

R. Darrell Kelso (Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 12 day of October, 19 92

My Commission Expires:



Irene Neff Notary Public