

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 8 Twp. 18 Rge. 25W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE SE

Lease Owner DONALD C. SLAWSON

Lease Name Elmore 'E' Well No. 1

Office Address 408 One Twenty Building - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-2- 19 65

Application for plugging filed 9-2- 19 65

Application for plugging approved 9-2- 19 65

Plugging commenced 9-2- 19 65

Plugging completed 9-2- 19 65

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty - Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4428 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 600', set plug, 1/4 sx of hulls, 20 sx cement
Mud to 240', set plug, 1/4 sx of hulls, 20 sx cement
Mud to 40', set plug, 1/4 sx of hulls, 10 sx cement
2 sx of cement in the rat hole

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.

Address 408 One Twenty Building - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
DONALD C. SLAWSON (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

408 One Twenty Building - Wichita, Ks.

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of September, 19 65

My commission expires August 25, 1968

Ella Priess

Notary Public.

WELL LOG

Company: DONALD C. SLAWSON
 408 One Twenty Building
 Wichita, Kansas 67202

Farm: Elmore 'E' #1
 C SE SE, Section 8-18-25W
 Ness County, Kansas

Total Depth: 4428' Elev. 2474 K.B.

Commenced: August 23, 1965
 Completed: September 2, 1965

Contractor: Slawson Drilling Company, Inc.

Casing: 8 5/8" @ 303' with 230 sacks of cement

| | |
|-----------|----------------------|
| 0-60 | Surface clay |
| 60-825 | Lime, Shells & Shale |
| 825-1195 | Shale & Shells |
| 1195-1465 | Sand |
| 1465-1560 | Shale & Lime |
| 1560-1727 | Shale & Shells |
| 1727-1759 | Anhydrite |
| 1759-2200 | Shale & Shells |
| 2200-2570 | Lime & Shale |
| 2570-2920 | Lime |
| 2920-2950 | Shale & Lime |
| 2950-3215 | Lime & Shale |
| 3215-3465 | Shale & Lime |
| 3465-3570 | Lime |
| 3570-3755 | Lime & Shale |
| 3755-3781 | Shale |
| 3781-4134 | Lime |
| 4134-4305 | Lime & Shale |
| 4305-4335 | Lime |
| 4335-4397 | Lime & Shale |
| 4397-4428 | Miss. |
| 4428 | Total Depth |

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1965

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)SS:
 COUNTY OF SEDGWICK)

I, Donald C. Slawson, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Elmore 'E' #1 well.


 DONALD C. SLAWSON

Subscribed and sworn to before me this 21st day of September, 1965.


 Ella Priess, Notary Public

My Commission Expires:
August 25, 1965