


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County, Sec. 11 Twp. 17S Rge. 26W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner Pickrell Drilling Company
Lease Name Mossiman "A" Well No. 1
Office Address 2820 Paseo Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed Dec 5th 19____
Application for plugging approved Dec 6th 19____
Plugging commenced December 5, 1962 19____
Plugging completed December 9, 1962 19____
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4571 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	307	none
				5 1/2	none	2530

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaned out callar.
Rigged up ~~XXXXX~~ and sanded to 4500', dumped 5 sx. cement and worked pipe.
Loaded hole with water and shot @ 2700'. Pulled pipe.
Mixed and pumped 22 sacks mud and 20 sacks cement @ 750'. Pulled 550' and pumped 20 sx. @ 200'. Pulled pipe and capped well with 10 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of November, 1962

My commission expires July 23, 1966

Carolyn Herren
Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Bldg.
 Wichita 2, Kansas
 LOCATION: MOSLIMAN #1 - C SE SW, Sec. 11-17S-26W
 Ness County, Kansas

Rotary Drilling Commenced. 10/13/61
 Rotary Drilling Completed. 10/26/61

CONTRACTOR: PICKRELL DRILLING COMPANY
 Wichita, Kansas

CASING RECORD: 307' (8 jts.) 8 3/8" 20# surface casing w/165 sacks cement. Circulated.
 4569' (145 jts.) 4 1/2" 9.5# Smis. Casing cemented w/85 sacks cement.
 Completed 10:15 A.M. 10/26/61

LOG

(Figures indicate bottom of formation -- measurements from top of rotary casing)

40'	Clay & Post Rock		
165'	Sand & Clay		<u>Circulated for Samples</u>
425'	Black Shale		4415'
620'	Sandy Shale		4425'
760'	Grey Shale		4448'
900'	Sandy Shale		4495'
1150'	Blue Gray Shale		4506'
1200'	Red Beds & Shale		4513'
1315'	Shale & Shells		4520'
1335'	Blaine		4530'
1400'	Shale & Shells		4535'
1700'	Shale		4540'
1915'	Shale & Shells		4543'
1955'	Anhydrite		4570'
2250'	Shale & Shells		
2755'	Lime & Shale	<u>Slope Test</u>	
2975'	Lime	1700'	0°
3655'	Lime & Shale	2542'	0°
3735'	Lime, Shale & Sand	3655'	0°
3880'	Lime & Shale	4448'	0°
3960'	Lime		
4055'	Lime & Shale	<u>S. L. M.</u>	
4197'	Lime	1810'	
4515'	Lime & Shale	2975'	
4517'	Cherty Conglomerate	4055'	
4570'	Mississippi R.T.D.		

RECEIVED
 STATE CORPORATION COMMISSION

DEC 17 1962

CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, Gerald W. Pike, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well, as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By Gerald W. Pike
 Gerald W. Pike Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 30th day of October, 1961, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared Gerald W. Pike, to me known to be the person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Witness my hand and seal of office the day and year last above written.

Notary Public for Kansas September 24 1962

Maxine Johnson
 Maxine Johnson Notary Public