

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ness SEC. 7 TWP. 17S RGE. 26W E/W
Location as in quarters or footage from lines:
SW NE NE

			*

Locate Well
correctly on above
Section Platt.

Lease Owner D. R. Lauck Oil Company, Inc.
Lease Name Arnold Well No. 1
Office Address 221 S. Broadway, Suite 400, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed October 28, 1982
Application for plugging filed 11/12/82
Plugging commenced 10-28-82
Plugging completed 10-28-82
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom _____ T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0'	301'	8-5/8"	293.91'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged with 70 sacks cement at 1250';
40 sacks cement at 300'; bridge plug
and 10 sacks cement at 40'; and 10 sacks
cement circulated in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1982

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


John D. Knightley (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
221 S. Broadway, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1982

[Signature]
Notary Public.

My Commission expires: March 12, 1983



D. R. Lauck Oil Company, Inc. - Arnold #1
 221 S. Broadway, Suite 400 SW NE NE Sec. 7-17S-26W
 Wichita, Kansas 67202 Ness County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
 221 S. Broadway, Suite 400
 Wichita, Kansas 67202

Commenced: October 19, 1982
 Completed: October 28, 1982

Drillers Log

Shale	320
Clay & Shale	1280
Shale & Shells	2019
Anhydrite	2050
Shale & Shells	2190
Shale	2515
Shale & Shells	3225
Shale	3540
Shale & Lime	3965
Lime	4650 RTD

Casing: 301' 8-5/8" cemented with 225 sacks Common Cement,
 2% Gel, 3% CaCl₂.

RECEIVED
 STATE CORPORATION COMMISSION

NOV 17 1982

CONSERVATION DIVISION
 Wichita, Kansas