


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County. Sec. 22 Twp. 17S Rge. 24 (6/) (W)

Location as "NE/CNW*SW*" or footage from lines. SW NE
Lease Owner Barnett Drilling, Inc.
Lease Name Mishler Well No. 1
Office Address 409 First National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 18 1959
Application for plugging filed June 18 1959
Application for plugging approved June 18 1959
Plugging commenced June 18 1959
Plugging completed June 18 1959
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production - 19-
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4576 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set a wooden plug at 600 feet and dumped 20 sacks cement on top; mixed through drill pipe. Set another plug at 200 feet and dumped 15 sacks cement on top; mixed through drill pipe. Filled hole with mud to 40 feet. Set plug which was wired to the surface, dumped 10 sacks cement on top. Dumped 5 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnett Drilling, Inc.
Address 409 First National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Louise Burnett (employee of owner) ~~owner or operator~~ of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Louise Burnett
409 First National Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 1959

My commission expires February 27, 1960

Mildred J. Wilks
Notary Public.

PLUGGING
FILE SEC. 22 T. 17 R. 24
BOOK PAGE 47 LINE 45

BARNETT DRILLING, INC.
WELL LOG OF MISHLER NO. 1,
A/C SW NE, SECTION 22-17S-24W
NESS COUNTY, KANSAS.

Date Started: June 4, 1959

Completed: June 18, 1959

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>
-0-	30	Post Rock
50	70	Shale
70	80	Sand
80	221	Shale and Shells
221	550	Shale
550	610	Sand
610	890	Shale and Shells
890	1230	Shale
1230	1270	Shale and Shells
1270	1450	Sand
1450	1785	Shale and Shells
1785	1810	Anhydrite
1810	1850	Shale and Shells
1850	2230	Shale
2230	2775	Shale and Lime
2775	3385	Lime
3385	3480	Lime and Shale
3480	3615	Shale and Chalk Lime
3615	4576	Lime (Total Depth) (D&A)

RECEIVED
 STATE OF KANSAS COMMISSION
 JUN 23 1959
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8-5/8" Surface casing at 221 feet;
 Cemented with 150 sacks cement.

STATE OF KANSAS)
) ss.
 COUNTY OF SEDGWICK)

I, Louise Burnett, do hereby certify that the above and foregoing is a true and correct copy of the log of the Mishler No. 1, SW NE of Section 22-17S-24W, Ness County, Kansas, as reflected by the files of the Barnett Drilling, Inc.

BARNETT DRILLING, INC.

By Louise Burnett
 Office-Manager

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 22nd. day of June, 1959.

Mildred F. Willis
 Notary Public

My commission expires February 27, 1960.

PLUGGING
 FILE SEC 22 T 17 R 24W
 BOOK PAGE 47 LINE 45