


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 13 Twp. 17 Rge. 21 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW SW
Lease Owner Chief Drilling Company
Lease Name Elmore G#1 Well No.
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/18/67 19
Plugging completed 9/20/67 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 4160 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	407'	none
				5-1/2"	4159'	3297'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4160', ran sand to 4075' and dumped 5 sacks of cement. Cut off poor boy head, had hole loaded, shot pipe at 3277' and it came loose. Pulled 103 joints of 5 1/2". Had collar welded on surface, Sun Cementing Company pumped 23 sacks of mud, 100 sacks of cement and 7 sacks of mud. Capped well with 20 sacks of cement.

PLUGGING COMPLETE.

RECEIVED BY ME
9/21/67
1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of September, 1967

My commission expires February 15, 1971

Margaret Ditcher
Notary Public.

15.135.30349.00.00

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas 67530

ELMORE "G" #1
NW SW Section 13-17S
Ness County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 8-22-67
Completed: 8-31-67.

Casing Record: 8-5/8" @ 407' w/225 sacks 60/40 Pozmix
5-1/2" @ 4159' w/10 bbls. salt flush, 150 sacks 60/40
Salt Saturated Pozmix

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1967
CONSERVATION DIVISION
WYDOWITZ, KANSAS

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Clay	0	60	2167 Gr.
Shale	60	225	2169 D.F.
Shale & Sand Streaks	225	355	2172 K.B.
Shale	355	890	
Sand	890	1115	
Shale, Shells & Red Bed	1115	1434	
Anhydrite	1434	1466	
Shale & Lime	1466	1635	Anhydrite 1432 (+ 740)
Shale & Shells	1635	1940	Heebner 3573 (-1401)
Shale & Lime	1940	2426	Toronto 3593 (-1421)
Lime	2426	2657	Lansing 3612 (-1440)
Lime & Shale	2657	3326	Base Kansas City 3906 (-1734)
Lime	3326	3576	Pawnee 3980 (-1808)
Shale & Lime	3576	3615	Ft. Scott 4054 (-1882)
Lime	3615	3905	Cherokee Shale 4063 (-1891)
Lime & Shale	3905	3981	1st Sand Not Developed
Lime	3981	4062	2nd Sand 4080 (-1908)
Shale & Sand	4062	4126	3rd Sand 4100 (-1928)
Chert	4126	4160	Conglomerate 4117 (-1945)
Rotary Total Depth	4160		Mississippi 4126 (-1954)
			Total Depth 4161 (-1989)

STATE OF KANSAS, COUNTY OF BARTON) SS


I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NW SW Section 13-17S-21W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 1st day of September, 1967.

Carmen R. Cook
Carmen R. Cook, Notary Public



Commission expires: December 12, 1970.