

15.135.00473.00.00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

Completion Date:  
June, 1944 6/85

API NUMBER N/A (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Sohio Petroleum Company OPERATORS LICENSE NO. 6854

ADDRESS 50 Penn Place, Suite 1100; Oklahoma City, OK73118 PHONE # (405)-848-7571

LEASE (FARM) Frevele 'A' WELL NO. 2 WELL LOCATION SW SE COUNTY Ness

SEC. 22 TWP. 16S RGE. 25 (E) or (W) (W) TOTAL DEPTH 4900' PLUG BACK TD ±4320

Check One:

OIL WELL        GAS WELL        D & A        SWD or INJ WELL X DOCKET NO. 58,293-C (C-6626)

SURFACE CASING SIZE 10-3/4" SET AT 309' CEMENTED WITH 150 SACKS  
Liner Size 5-1/2" " 1698' " 200  
CASING SIZE 7" SET AT 4537' CEMENTED WITH 175 SACKS

PERFORATED AT 4024-42'

CONDITION OF WELL: GOOD        POOR        CASING LEAK        JUNK IN HOLE X

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Load csg. w/±150 Bbl gelled water, spot 20 sx 60/40 poz @ 3800'. Pull tbg to 1990', spot 20 sx 60/40 poz. Pull up to 1000'; spot 20 sx 60/40 poz. Pull up to 400' and fill 5-1/2" w/60/40 poz. Tie onto 10-3/4-7" annulus and pump in 60/40  
(If additional space is needed use back of form) (OVER)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be arranged with state plugging agent (Richard Lacy or Paul Luthi).

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Don Wilson or Cecil Stangle PHONE # (913) 637-5290 RECEIVED STATE CORPORATION COMMISSION

ADDRESS RR, Gorham, KS 67640 MAY 1985

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. 5208 CONSERVATION DIVISION  
Wichita, Kansas

ADDRESS Box 428, Hays, KS 67601 PHONE # (913) 625-3431

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: \_\_\_\_\_  
(Operator or Agent)

DATE: \_\_\_\_\_

0

Method of Plugging (Continued)

poz w/hulls until pressure observed. Fill annulus to surface. Cut csg off 3 ft. below GL and weld on steel plate.

State of Kansas



HN CARLIN  
 CHAEL LENNEN  
 RGALEE WRIGHT  
 ITH R. HENLEY  
 DITH A. MCCONNELL  
 IAN J. MOLINE

Governor  
 Chairman  
 Commissioner  
 Commissioner  
 Executive Secretary  
 General Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 200 Colorado Derby Building  
 202 West 1st Street  
 WICHITA, KANSAS 67202-1286

Extension

~~THIS NOTICE~~ ~~THIS NOTICE~~

NOV 8 1985 AUG 8 1985

EXPIRES EXPIRES

May 8, 1985

WELL PLUGGING NOTICE

Frevele "A", #2 (SWD)  
 SW SE  
 Sec. 22-16S-25W  
 Ness County

Sohio Petroleum Company  
 50 Penn Place, Ste. 1100  
 Oklahoma City, OK 73118

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).