

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Ness County, Sec. 22 Twp. 17S Rge. (E) 21W(W)  
C NW NE

Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner Okmar Oil Company  
Lease Name Connor Well No. 1  
Office Address 1130 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-31 1972  
Application for plugging filed 5-31 1972  
Application for plugging approved 5-31 1972  
Plugging commenced 5-31 1972  
Plugging completed 5-31 1972  
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4191 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	262'	8-5/8"	254'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fluid to 450', 70 sx cement; after plug;  
Fluid to 40', 1/2 sx hulls, plug, 10 sx cement;  
Two sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 9 1972

CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.  
Address 737 First National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF \_\_\_\_\_, SS.  
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson  
737 First Nat'l Bank Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of June, 19 72



Ella Priess  
Ella Priess Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 9 1972

CONSERVATION DIVISION  
Wichita, KansasDRILLERS' LOGOKMAR OIL COMPANY  
No. 1 Connor  
C NW NE, Sec. 22-17S-21W  
Ness County, Kansas

Elev: 2179 K.B.

Commenced: 5-24-72  
Completed: 5-31-72Surface Casing: 254' of  
8-5/8" cemented w/190 sx  
cement, 3% cc. 5-24-72FORMATIONDEPTH

Surface Hole	0 - 262
Shale	262 - 285
Shale & Sand	285 - 900
Sand	900 - 1120
Red Bed	1120 - 1452
Anhydrite	1452 - 1484
Shale	1484 - 1960
Lime	1960 - 3050
Lime & Shale	3050 - 3320
Lime	3320 - 4090
Lime & Shale	4090 - 4108
Lime	4108 - 4137
Sand	4137 - 4141
Lime	4141 - 4191 T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state this 8th day of June, 1972.

My Commission Expires:  
August 25, 1972

*Ella Priess*  
Ella Priess, Notary Public