

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pawnee County. Sec. 8 Twp. 20S Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Robinowitz Oil Co.

Lease Name Stump Well No. _____

Office Address 1322 E. 50th Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-31-66 19 66

Application for plugging filed 5-31-66 19 _____

Application for plugging approved 5-31-66 19 _____

Plugging commenced 11:30 AM 5-31 19 66

Plugging completed 1:00 PM 5-31 19 _____

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production none 19 66

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey Hays, Kansas

Producing formation none Depth to top _____ Bottom _____ Total Depth of Well 3895 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Soil Sand & Shale		0	299	8 5/8"	299	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 480' Set plug and cemented with 25 sacks through drill pipe with cement truck. Plug at 270'. Cemented through drill pipe with 20 sacks cement with Pump truck, Set plug at 40' with 10 sacks through drill pipe. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 6 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & B DRILLING, INC.
Address 548 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Laher

548 Petroleum Bldg. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 1966

My commission expires October 30, 1967
Virginia Parker
Notary Public.

B & B DRILLING, INC.

15.145.30091.0000

548 Petroleum Building

Wichita, Kansas 67202

June 3, 1966

DRILLERS LOG

Re: #1 Stump
SW SW SW Sec. 8-20S-6W
Pawnee County, Kansas

COMPANY: ROBINOWITZ OIL COMPZNY
CONTRACTOR: B & B DRILLING, INC.
TOTAL DEPTH: 3895'
COMMENCED: May 23, 1966
COMPLETED: May 31, 1966

RECEIVED
STATE CORPORATION COMMISSION
JUN - 6 1966
CONSERVATION DIVISION
Wichita, Kansas

0	299	Soil Sand & Shale (Surface Hole)
299	570	Shale
570	1045	Shael & Redbed
1045	1174	Shale
1174	1198	Anhydrite
1198	2381	Shael & Lime
2381	3581	Lime & Shale
3581	3795	Lime
3795	3888	Shale & Conglomerate
3888	3895	Lime (Abb)
	3895	Total Depth

We certify the above and foregoing to be true and correct copy of the log on the #1 Stump, located in Pawnee County, Kansas

B & B DRILLING, INC.

Bill Baker
President

Virginia Parker
Notary Public

Subscribed and sworn to before me on this 3rd day of June, 1966

Oct. 30, 1967