

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County Sec. 7 Twp. 20 Rge. 16 ~~20E~~ (W)

Location as "NE/CNW*SW*" or footage from lines NE NW NE
Lease Owner Shelley-Miller Drilling, Inc.
Lease Name Russell Well No. 1
Office Address 205 Miller Bldg., Wichita 2
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 6-15 1963
Application for plugging filed 6-15 1963
Application for plugging approved 6-15 1963
Plugging commenced 6-15 1963
Plugging completed 6-15 1963
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Pawnee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3835 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1140	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 420' w/20 sax cement
Middle Plug @ 180' w/20 sax cement
Top Plug @ 35' w/10 sax cement

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Woodman & Tannitti Drilling Co.
Address 706 Union Nat'l. Bldg., Wichita 2

STATE OF Kansas, COUNTY OF Sedgwick, ss.
K. T. Woodman (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) X. T. Woodman
706 Union Nat'l. Bldg., Wichita
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 63

My commission expires Oct. 10, 1963 Frances H. Solomon Notary Public.

INVOICED
DATE 6/21/63
INV. NO. 1754

15.145.00540.0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Shelley-Miller Drilling, Inc.

SEC. 7 T. 20 R. 16W
 LOC. NE NW NE

FARM Russell NO. 1

TOTAL DEPTH 3835'

COUNTY Pawnee
 KANSAS


COMM. 6-4-63

COMP. 6-15-63

SHOT OR TREATED

CONTRACTOR Woodman-Iannitti Drilling Co.

ISSUED



CASING

20	10	
15	8	5/8 @ 1140 w/450 sax cement
12	6	
13	5	

ELEVATION 2075 RB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	160	Clay
	180	Red Bed & Shale
	518	Streaks of Sand & Shale
	675	Sand
	1126	Red Bed & Shale
	1155	Anhydrite
	1400	Red Bed
	1645	Salt Shale
	1895	Shale
	2140	Shale & Lime
	2260	Broken Lime
	2290	Hard Lime
	2690	Lime
	2860	Lime & Shale
	3800	Lime
	3813	Conglomerate
	3835	Arbuckle

RECEIVED
 STATE CORPORATION COMMISSIONER

JUN 18 1963

CONSERVATION DIVISION
 Wichita, Kansas

I certify the above to be a true and correct copy of the Driller's Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING CO.

By: K. T. Woodman
 K. T. Woodman