

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 1 S. Market, Room 2078
 Topeka, KS 67202
 KANSAS CORPORATION COMMISSION

WELL PLUGGING RECORD
 K.A.R.-02-3-117

15-053-01785-00-00
 API NUMBER Drilled 1941
 LEASE NAME Grounds
 WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

660 Ft. from S Section Line
330 Ft. from E Section Line
 SEC. 12 TWP. 17 RGE. 10W (E) or (W)

OPERATOR Mike Kelso Oil, Inc

ADDRESS P.O. Box 467 Chase, Kansas 67524

COUNTY Ellsworth

PHONE (620) 938-2943 OPERATORS LICENSE NO. 31528

Date Well Completed _____

Character of Well Oil

Plugging Commenced 3-27-02

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Plugging Completed 3-28-02

The plugging proposal was approved on _____ (date)

Virgil Clothier (KCC District Agent's Name).

ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3280'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	465'	None
				5-1/2"	3273'	520'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from _____ feet to _____ feet each stage.
Plugged off bottom with sand to 3220' and 5 sacks cement. Pipe parted @520'. Layed down casing, ran 2" tubing to 850', pumped 50 sacks cement, pulled up to 515', pumped 35 sacks cement, pulled up to 250' and circulated 115 sacks cement to surface. 60/40 pos. 4% gel.
 Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike Kelso Oil, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 8th day of April XX9 2002

[Signature]
 Notary Public

My Commission Expires:



OR