


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 1 Twp. 19S Rge. 25 (W)

Location as "NE/CNW/SW" or footage from lines NE SE
Lease Owner Sunray DX Oil Co.
Lease Name Alden Miner Well No. 1
Office Address Box 729, Great Bend
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-17 1964
T Application for plugging filed 5-18 1964
19S Application for plugging approved 5-20 1964
Plugging commenced 5-17 1964
Plugging completed 5-17 1964
Reason for abandonment of well or producing formation
No commercial oil found



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 4497 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	422	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set cement plug per Mr. Elden Petty's instructions as follows:

- 25 sacks at 540'
- 25 sacks at 240'
- 10 sacks in top of 8-5/8" casing. Job completed 3:00 AM 5-17-64

All intervals between cement plugs filled with 9.8# mud laden fluid.

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company
Address Wichita, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
C. C. SHREVE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. C. Shreve, District Manager

(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of May, 1964

D. L. Jackson
Notary Public.

My commission expires February 22, 1967



Sunray DX Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
May 20, 1964

Contractor: Stickle Drilling Company
Date Commenced: May 2, 1964
Date Completed: May 17, 1964

Alden Miner No. 1
NE SE Section 1-19S-25W
Ness County, Kansas

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Shale	315
Shale and shells	1200
Red bed and shale	1660
Anhydrite	1690
Shale and shells	1848
Shale and sand	2335
Lime and shale	2520
Shale and lime	2705
Lime and shale	3196
Shale and chalk	3308
Lime and shale	3620
Shale and lime	3815
Lime and shale	4004
Lime	4245
Lime and shale	4365
Lime and chert	4386
Lime	4411
Dolomite and lime	4497 TD

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1964

CONSERVATION DIVISION
Wichita, Kansas

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray DX Oil Company's Alden Miner No. 1 Well, NE SE Section 1-19S-25W, Ness County, Kansas

Fred E. Stickle
FRED E. STICKLE

M. Wensley
Notary Public

My Commission Expires January 11, 1967