

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ness County. Sec. 29 Twp. 19S Rge. (E) 21(W)  
Location as "NE/CNW&SW&" or footage from lines C NW NE  
Lease Owner Pickrell Drilling Company  
Lease Name Rein "C" Well No. 1  
Office Address 705 4th National Bank Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 17, 1965  
Application for plugging filed April 17, 1965  
Application for plugging approved April 17, 1965  
Plugging commenced April 17, 1965  
Plugging completed April 17, 1965  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4462 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	359'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 240', set plug, cemented with  
25 sacks cement. Heavy mud to 40', set plug,  
cemented with 10 sacks cement to bottom of  
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

4-23-65 APR 23 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 4th National Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. SEBITS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits  
705 4th National Bank Bldg, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 19 65

My commission expires June 21, 1966  
Maxine Blackman Notary Public.

**ROTARY DRILLING LOG**

COMPANY: PICKRELL DRILLING COMPANY  
705 4th National Bank Bldg.  
Wichita, Kansas

Rotary Drilling Commenced 4--5-65

Rotary Drilling Completed 4-17-65

LOCATION: Rein "C" No. 1, C NW NE Section 29-19-21W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: (16 jts) 8 5/8" surface casing set at 359' cemented with 180 sacks cement. Circulated. Completed 7:00 P.M. April 5, 1965. No oil string run, D & A.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

115	Top soil & post rock.	<u>C. F. S.</u>
305	Shale & Shells	4310
330	Sand	4322
665	Shale	4399
832	Red Beds & Shale	4404
841	Blaine	4409
928	Shale	4414
1140	Sand	4419
1490	Red Beds, Shale & Shells	4422
1525	Anhydrite	4462
1925	Shale & Shells	
2390	Lime & Shale	
2785	Lime	<u>Slope Tests</u>
3620	Shale & Lime	2500
3755	Lime, Shale, Sandy	3005
3912	Shale & Lime	3565
4343	Lime	4080
4404	Lime, Shale & Chert	
4414	Conglomerate	
4462	Mississippi - RTD	<u>S. L. M.</u>
		4768
		4054
		4392

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 23 1965

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 20th day of April, 19 65, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman  
Maxine Blackman, Notary Public