

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-159-21,286.0000 *2*200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Templeton Energy Corporation
Complete Address 850 The Main Bldg, 1212 Main St, Houston, Texas
Lease Name Tobias Well No. 1
Location 660' FWH 660' FSL SW SW Sec. 9 Twp. 20 Rge. 7 (East) (West)
County Rice Total Depth 3320'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D & A ☒Other well as hereafter indicated ☐

Plugging Contractor Allen Drilling Co. and San Oilwell Cementing, Inc.
Address Box 1389, Great Bend, Kansas License No.

Operation Completed: Hour: 8:30 AM Day: 1 Month: October Year: 1981Plugging Operations attended by Agent? All ☐ Part ☐ None ☒The above well was plugged as follows: 8 5/8" - 269' 225 sacks 50-50 Pozmix

Hole circulated and Filled with mud. 60 sacks cement pumped through drill pipe at 480'. 40 sacks cement pumped through drill pipe at 260'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement. Water Well cemented with 5 sacks cement.

Cement used: 50-50 Pozmix w/2% gel and 3% cc

I hereby certify that the above well was plugged as herein stated.

RECEIVED
INVOICED
STATE CORPORATION COMMISSIONSigned: *William J. Loman*

Conservation Division Agent

DATE 11-24-81 71981 10-7-81INV. NO. 8487-6 CONSERVATION DIVISION

Wichita Kansas