



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 APR 29 1968
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

April 15, 1968

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ben Thompson of Pipe Pullers, Inc. has this

date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Banner Oil Company

Complete Address: Box 316, Claflin, Kansas 67525

Lease Name: Peterman Well No. 2

Location: SE NE NE Sec. 11 Twp. 17 Rge. 10 (E) (W) X

County: Ellsworth Total Depth 3297' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Thompson was instructed to plug the well as follows:

Fill hole with sand to 3250' and cement with 5 sacks.

Pull 5 1/2" casing to 600'. Pump 5 sacks gel mud through casing at 600'.

Pull casing to 500'. Pump 25 sacks cement through casing at 500'. Pull

casing to 325'. Pump 5 sacks gel mud through casing at 325'. Pull casing

to 225'. Pump 25 sacks cement though casing at 225'. Pull remainder of

casing. Fill hole with mud to 40'. set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

 Conservation Division Agent