

State of Kansas



Form CP-2

15.053.20576.0006

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

February 26, 1980

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY

Governor
Chairman
Commissioner
Commissioner

Carol J. Larson, Executive Secretary

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draney of Duke Drilling Co. has this
date requested permission to plug the following described well:

Mr. Draney guarantees payment of the plugging fee.

Operator's full Name: Petroleum Energy Inc.

Complete Address: 710 One Twenty Bldg., Wichita, Kansas 67202

Lease Name: Krenke Well No. 1

Location: C W/2 E/2 NE Sec. 11 Twp. 17 Rge. 10 (W) X

County: Ellsworth Total Depth 3303 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draney was instructed to plug the well as follows:

8 7/8" - 262' cem. Circ. Fill hole with mud. Pump 40
Sacks cement through drill pipe at 500'. Pump 25
Sacks cement through drill pipe at 250'. Fill hole
with mud to 40'. Push plug and 1/2 sack cement to 40'
and cap hole with 10 sacks cement. Bridge mouth hole
and cement with 2 sacks.

Very truly yours, CONSERVATION DIVISION
Wichita, Kansas

Alfred J. Larson
Conservation Division Agent