



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 10 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Roger L. Messman of Messman-Rinehart Oil Co. has this date requested permission to plug the following described well:

Mr. Messman-Rinehart Oil guarantees payment of the plugging fee.  
Company

Operator's full Name: Messman-Rinehart Oil Company

Complete Address: 1432 Wichita Plaza, Wichita, Kansas 67202

Lease Name: Unruh "B" Well No. # 1

Location: NE NE NW Sec. 29 Twp. 20 Rge. 15 (E)(W) W

County: Barton Total Depth 3851 Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Russ Sullivan was instructed to plug the well as follows:

8 5/8" csg. 736' Cwc. Perf. 3796'.

Sanded hole back to 3760' & dumped 4 sax cement with dump bailer.

Pulled pipe. Squeezed well with 3 sax hulls, 20 sax mud, & 100 sax

cement with Globe Cementing Company's pump truck, cementing from 330'

to base of cellar.

Very truly yours,

Dore L. Linn  
Conservation Division Agent