

State of Kansas



15.145.20079.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Howard of Sage Drlg. has this

date requested permission to plug the following described well:

Mr. Howard guarantees payment of the plugging fee.

Operator's full Name: Appleton Oil Co.

Complete Address: 506 Beacon Bldg., Tulsa, Okla.

Lease Name: Stump Well No. 1

Location: SW NE SW Sec. 8 Twp. 20 Rge. 16 (E)(W) X

County Pawnee Total Depth 1628 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Howard was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace
50 sc cement thru drill pipe. Heavy mud to 300' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo F. Massey
Conservation Division Agent