

State of Kansas



15.145.30091.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN - 1 1966

Conservation Division
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lahar of B - B drilling Co. has this

date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Robinowitz Oil Co.

Complete Address: 1322 E 50 th. Tulsa, Okla.

Lease Name: Stump Well No. 1

Location: SW - SW - SW Sec. 8 Twp. 20 Rge. 16 (E)(W) X

County Pawnee Total Depth 3895 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Gun pits, circulate hole with heavy mud, set cementing plug at
480 ~~500~~ Ft. and displace 25 sax cement thru drill pipe. heavy mud
to 290 Ft. set cementing plug and displace 20 sax cement thru
drill pipe. heavy mud to 40 Ft. Set cementing plug, 1/3 sax hulls
and 10 sax cement to base of cellar. Plug rat hole with 2 sax cem.

Very truly yours,

Geo Massey
Conservation Division Agent