



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 29 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Crowe of Garvey Drlg. has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Appleton Oil Co.

Complete Address: 506 Beacon Bldg. Tulsa, Okla.

Lease Name: Hagerman Well No. 1

Location: NE NE NW Sec. 7 Twp. 20 Rge. 16 (E)(W) X

County: Pawnee Total Depth 3884' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:
 Gun pits, circulate heavy mud, set cementing plug at 480' and displace
 70 sc cement thru drill pipe. Heavy mud to 300' set cementing plug and
 displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
 plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
 with 2 sc cement.

Very truly yours,

Russ J. Marney
 Conservation Division Agent