

State of Kansas



15.135.30360.00.01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 30 1967  
10-30-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Pfannenstiel of Leben Drlg. Co. Inc. has this  
date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: McClure Oil Co.

Complete Address: 1301 Plaza Bldg. Wichita, Kansas

Lease Name: Antener Well No. 1

Location: NE NE Sec. 6 Twp. 19 Rge. 24 (E)(W) X

County Ness Total Depth 4440' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole       
OWWO

Mr. Pfannenstiel was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace  
170 sc cement thru drill pipe. Heavy mud to 390' set cementing plug and  
displace 26 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with  
2 sc cement.

Very truly yours,

Ben F. Massey  
Conservation Division Agent