

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1966

Dear Sir:

Mr. Pfannenstiel of Leben Drilling Co., Inc. has this

date requested permission to plug the following described well:

CONSERVATION DIVISION
Wichita, Kansas

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: McClure Oil Co.

Complete Address: 1301 Plaza Building, Wichita, Kansas

Lease Name: Antenen Well No. 1

Location: C NE NE Sec. 6 Twp. 19 Rge. 24 (E)(W) X

County Ness Total Depth 4440 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600 Ft.
and displace 25 sax cement thru drill pipe. Heavy mud to 400 Ft.
set cementing plug and displace 20 sax cement thru drill pipe.
Heavy mud to 40 Ft. set cementing plug, 1/3 sax hulls, and 10 sax
cement to base of celler. Plug rat hole with 2 sax cement.

Very truly yours,

Leo Messing
Conservation Division Agent