

State of Kansas



15.135.20882.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1974

CONSERVATION DIVISION
Wichita, KansasVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:Mr. Pulley guarantees payment of the plugging fee.Operator's full Name: Mull Drilling Company, Incorporated,Complete Address: 415 Page Court, 220 W. Douglas, Wichita, Kansas.Lease Name: Antenen Well No. A-1Location: CSE-NE Sec. 6 Twp. 19 Rge. (E)(W) 24County: Ness Total Depth 4417' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Pulley was instructed to plug the well as follows:248'--8 5/8" Surface casing, cement circulated with 200 Sx.
4353'--4 1/2" casing cemented with 100 Sx. Well plugged back to 4321'.
Top of perforations @ 4289'.Push plug to 4250' and sand to 4225 then set 4 Sx. cement with dump bailer.
Pull casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu.
Ft. cement, staged.

Very truly yours,

Conservation Division Agent