

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,623-00.00

SE SW NE, SEC. 32, T 17 S, R 24 W/E
N SE Corner of
2970 feet from ~~XXX~~ section line
W SE Corner of
1650 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6177

Lease Name Michaelis Well # 1

Operator: Foxfire Exploration, Inc.

County Ness

Name & Address 10403 West Colfax Ave, # 740

Well Total Depth 4360 14170 feet

Lakewood, CO 80215

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 348

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Foxfire Drilling Co., Inc. License Number 8430

Address 10403 West Colfax Ave., # 740, Lakewood, CO 80215

Company to plug at: Hour: 6:00 am Day: 12 Month: September Year: 1984

Plugging proposal received from Jerry Fisher

(company name) Foxfire (phone) 913-743-5650

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1643' with 50 sx cement

2nd plug at 820' with 50 sx cement

3rd plug at 398' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Ryder Wiley
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:15 am Day: 12 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1643' with 50 sx cement, 2nd plug at 820' with

50 sx cement, 3rd plug at 398' with 50 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat

hole with 15 sx cement

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 9-21-84

Signed Ryder Wiley 50
(TECHNICIAN)

INV. NO. 3831

9-12 OCT 12 1984