

1-18-84 Wichita

15.135.00179.00.01

1050194

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 5-19-61
C SW SW, SEC. 5, T 17 S, R 22

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

feet from N/S section line
feet from W/E section line

Operator: A. Scott Ritchie
Name & Address: 125 North Market, Suite 950
Wichita, KS 67202

Lease Name Sekevec Well # 1
County Ness
Well Total Depth 1690 54.93 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated Replug well for an area of influence around new SWD well.

Plugging Contractor Cheyenne Well Service License Number 6454

Address Box 384, Ness City, KS 67560

Company to plug at: Hour: 8:00 am Day: 17 Month: April Year: 19 84

Plugging proposal received from Galen Babcock

(company name) A. Scott Ritchie (phone) 316-267-4375

were: Redrilled hole to 1700'. Circulated 39 viscosity mud to condition hole.

Spotted plugs through tubing. 1st plug at 1690' with 50 sx cement

2nd plug at 1000' with 70 sx cement 3rd plug at 300' with 50 sx cement

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:45 am Day: 17 Month: April Year: 19 84

ACTUAL PLUGGING REPORT Redrilled hole to 1700'. Circulated 39 viscosity mud to condition hole. Spotted plugs through tubing. 1st plug at 1690' with 50 sx cement, 2nd plug at 1000' with 70 sx cement, 3rd plug at 300' with 50 sx cement, 4th plug and 5th plug - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-20-84

INV. NO. 1200 J-17

RECEIVED STATE CORPORATION COMMISSION

APR 20 1984

Signed Richard W. Lacey (TECHNICIAN)

MAY 03 1984 CONSERVATION DIVISION

JUL 2 1984

FORM CP-2/3 Rev. 01-84