

15.135.00473.00.00

1 050673

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed June 1944

SW SE, SEC. 22, T 16 S, R 25 W/EX
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6854

Operator: Sohio Petroleum Company
Name & Address: 50 Penn Place
Suite 1100
Oklahoma City OK 73118

Lease Name Frevele "A" Well # 2
County Ness 159.25
Well Total Depth 4900' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10-3/4 feet 309

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number NA

Address Box 428, Hays KS 67601

Company to plug at: Hour: 10:00 am Day: 12/13 Month: November Year: 1985

Plugging proposal received from Rudy Herman

(company name) Sohio Petroleum Company (phone) 913-637-5290

were: Load hole w/ gell mud . spot 20 sx of cement at 3800' through tubing. Pull tubing to 1990' and spot 20 sx of cement. pull tubing to 1000' spot 20 sx of cement. Pull tubing to 400' and fill casing to surface with cement. Tie onto 10-3/4-7" annulus and try to pump cement. 7" production casing set @ 4537' 5 1/2" liner set @ 1698' to 0' cemented w/ 200s. 7" is supposed to be squeezed from 1000' to approx. 250'

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 4:45pm Day: 12/13 Month: November Year: 19 85

ACTUAL PLUGGING REPORT Loaded hole w/ gell mud. Spotted 20 sx of cement and 1sx of hulls at 3807'. Pulled tubing to 1990 and spotted 50 sx of cement and 1 sx of hulls. Pulled tubing to 1000' and spotted 20 sx of cement. Pulled tubing to 400 and filled casing to surface with cement. Tied unto 10-3/4 and 7" annulas and could not pump any cement. Annulas must be full of cement.

This well was a salt water repressuring well Docket #D-6626

Remarks: Halliburton pumped 6040 pozmix 6 %gel for cement (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-9-85

INV. NO 11324

RECEIVED STATE CORPORATION COMMISSION

NOV 18 1985

Signed Richard W. Lacey (TECHNICIAN)

CONSERVATION DIVISION

FORM CP-2/3 Rev 01-84