

1 120053

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 110' W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,924 00.00

TECHNICIAN'S PLUGGING REPORT

NW NE SE SEC. 34, T 16 S, R 21 W/E

2310 feet from S section line

1100 feet from E section line

J. R. Elmore

Operator License # 7250

Lease Name Estate Well # 1

Operator: Thomas W. Wiesner Oil Operations

County Ness 134.88

Name & Address 1904 Longfellow

Well Total Depth 4150 Mississippi feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling License Number 5302

Address 1720 KSB Building, Wichita, KS 67202

Company to plug at: Hour: 10:00 pm Day: 20 Month: September Year: 1985

Plugging proposal received from Walter Oden

(company name) Red Tiger (phone) 316-263-2371

Elevation 2215

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1502'

1st plug at 1525' with 50 sx cement

2nd plug at 620' with 60 sx cement

3rd plug at 290' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Don C. Ubel

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:30 pm Day: 20 Month: September Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1525' with 50 sx cement, 2nd plug at 620' with 60 sx

cement, 3rd plug at 290' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx

cement.

Remarks: Used 60/40 Pozmix 4% gel by BJ-Titan

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

do not observe this plugging.

SEP 27 1985

Signed Don C. Ubel (TECHNICIAN)

DATE OCT 03 1985

INV. NO. 10355

DEC 16 1985 CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 01-84