

1 051426

4-12 15,165,20658.00.82 210 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- Docket #D-19,208  
C W/2 NE, SEC. 31, T. 19, S, R 20 W/E  
3960 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5228  
Operator: Parrish Corporation  
Name & Address 100 S. Market, Ste. 200  
Wichita, KS 67202

Lease Name Hamzy Well # 4  
County Rush 155.18  
Well Total Depth 4775 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 12 Month: 4 Year: 19 91

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4521' w/250 sx cement, Open hole 4521-4775', Tubing fish at 2316'  
1st plug run tubing to 2316' and pump 75 sx cement, then 75 sx cement with 500 lbs.  
hulls mixed in, 2nd plug pump 50 sx cement at 1450' with 50 sx cement,  
3rd plug pump 80 sx cement at 700', 4th plug pump 40 sx cement at 330',  
5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 p.m. Day: 12 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug ran tubing to 2316' and pumped 75 sx cement and then 75  
sx cement with 500 lbs. hulls mixed in-65/35 Pozmix 10% gel,  
2nd plug pumped 5 sx gel and 80 sx cement at 780',  
3rd plug pumped 40 sx cement at 330',  
4th plug pumped 10 sx cement at 40'-60/40 Pozmix 6% gel.

Remarks: Used 65/35 10% gel and 60/40 6% gel by Allied. Recovered 780' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-22-91

INV. NO. 31642

STATE CORPORATION COMMISSION

APR 17 1991

Signed Richard W Lacey  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

4-17-91