

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- -

E/2 SW/4, Sec. 5, T 20 S, R 16 W/E

feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Almqvist Well # 1

Operator: Murfin Drilling Company
Name & Address
617 Union Center
Wichita, KS 67202

County Pawnee

Well Total Depth 3818 feet \$124.09

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 1128

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Packers License Number 6050

Address Box 176 Chase Kansas 67524

Company to plug at: Hour: 12:00 noon Day: 9 Month: June Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Bob Brennemen

(company name) Kelso Casing Packers (phone) _____

were: Sand Bottom to 3745 + dump 5 sx cement. Then pump down 8 5/8" with 3 hulls - 15 gel - 50 sx cement, 5 gel, + 1 Hull - release plug, 120 sx cement. Use 60/40 pozmix 2% gel / 3% cc

Signed Richard W. Lucey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 9 Month: June Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered in above paragraph

Maximum Pump pressure 850 psi

Shot in pressure 500 psi

Recovered 1928' of 5 1/2 production casing

San oil well cementing pumped the cement

Remarks: Mr. Bob Tarbotton gave plugging orders

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1983

I hereby certify that the above plugging instructions were given as ~~wherein stated~~ and that I (did / ~~did not~~) observe this plugging.

Signed Richard W. Lucey
(TECHNICIAN)

INVOICED

DATE 6-17-83

INV. NO. 4607-W