

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-00719.0000

NE SE SW, Sec. 5, T 20 S, R 16 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Almqvist Well # 2

Operator: Mortin Drilling Company
Name & Address: 617 Union Center
Wichita KS 67202

County Pawnee
Well Total Depth 3778 feet \$ 122.79
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1110'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pullers License Number 6050

Address Box 176 Chase Kansas 67524

Company to plug at: Hour: 2:00 pm Day: 9 Month: June Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Bob Brenneman

(company name) Kelso Casing Pullers (phone) _____

were: 60/40 poz mix 2% gel 3% cc Squeeze
down 5 1/2 casing with 1 sx hulls, 25 sx cement
15 gel - 50 sx cement - release plug - 125 sx cement
Sand bottom to 3725' + dump 5 sx cement

Signed Richard W. Lacy
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 pm Day: 9 Month: June Year: 19 83

ACTUAL PLUGGING REPORT Plugged as ordered in above paragraph

Maximum Pump pressure 1000 psi
Shut in Pressure 750 psi
San oil well cementing pumped the cement

Remarks: Mr. Bob Tarbotton gave plugging orders

RECEIVED
STATE CORPORATION COMMISSION

JUN 6-14-83
1983

I hereby certify that the above plugging instructions were given as hereinafter stated

and that I (did / did not) observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacy
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED
DATE 6-17-83
INV. NO. 4604-W