

7-19

120279

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,328.0000

NE NE SE, SEC. 31, T 20 S, R 16 W/E

2310 feet from S section line

330 feet from E section line

Lease Name Finger Well # 1

County Pawnee 123.86

Well Total Depth 3811 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1034

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Operator: AFG Energy, Inc.

Name & Address P.O. Box 605

Russell, KS 67665

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 9 a.m. Day: 19 Month: 7 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 3793' Open hole 3793-3811'

1st plug pump 2 sx hulls and 20 sx cement,

2nd plug pump 150 sx cement, 20 sx gel, 4 sx hulls, wiper plug.

RECEIVED
STATE CORPORATION COMMISSION

31 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:15 a.m. Day: 19 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 20 sx cement and pushed plug

to 3700',

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-700 psi and shut in 300 psi.

Recovered 2180' of 4 1/2" casing.

Remarks: Used 60/40 Pozmix 6% gel on top plug, common cement on bottom plug by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed *Richard W. Lacey*
(TECHNICIAN)

DATE 8-1-89

INV. NO. 25465