

1 051944 8-6

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-145-21,430.0000

C S/2 SW, SEC. 32, T 20 S, R 16 W/E  
660 feet from S section line  
1320 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418

Lease Name Fox Well # 1-32

Operator: Allen Drilling Company

County Pawnee

Name: P.O. Box 1389  
Address

Well Total Depth 3900 126.75 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1028

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Co. License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 3:45 p.m. Day: 6 Month: 8 Year: 1995

Plugging proposal received from Marvin Petz

(company name) Allen Drilling Co. (phone) 316-793-5877

Work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3825' with 50 sx cement, 2nd plug at 1060' with 50 sx cement,

3rd plug at 300' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7 p.m. Day: 6 Month: 8 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 3825' with 50 sx cement,

2nd plug at 1060' with 50 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Filled water well with cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 8-15-95

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 43314

8-6 NOV 02 1005

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 08 1995  
WICHITA, KANSAS  
8-8-95

