

1120785

4-27

15.145.19081.0001

76R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLGRADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-18,715

SW SW NE, SEC. 4, T 20 S, R 16 W/E
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6563

Lease Name Hagerman SWD Well # 1

Operator: Double B Oil, Inc.

County Pawnee 134.29

Name & Address 25515 N. Forest Road, #16

Well Total Depth 4132 feet

Rio Verde, AZ 85263

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 845

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Chase Well Service, Inc. License Number 6123

Address P.O. Box 355, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 27 Month: 4 Year: 1993

Plugging proposal received from Charles Steincamp

(company name) Chase Well Service, Inc. (phone) 316-793-9556

work: 5 1/2" at 3740' w/100 sx cement, 3" tubing at 3740', Open hole 3740-4132'
75 sx cement was pumped down 8 5/8" X 5 1/2" annulus

1st plug fill with cement to 3650',

2nd plug mud to 1100', cement 1100' to 0'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4 p.m. Day: 27 Month: 4 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped into 5 1/2" casing with 600 lbs. hulls, 75 sx cement, 20 sx gel. 100 lbs. hulls and 105 sx cement. Pumping pressure 0-500 psi and shut in 50 psi.

2nd plug pumped 20 sx cement in 8 5/8" X 5 1/2" annulus, cement circulated in cellar.

RECEIVED STATE CORPORATION CO

Remarks: Used 60/40 Pozmix 2% gel 2% cc by Allied. No casing recovery.

APR 30 1993

Additional description is necessary, use BACK of this form.

I (did / ~~did not~~) observe this plugging.

CONSERVATION DIVISION Wichita, Kansas

DATE 5-3-93

Signed [Signature] (TECHNICIAN)

INV. NO. 37644

INVOICED